CITY OF WALNUT CREEK

COMMUNITY DEVELOPMENT DEPARTMENT
CERTIFICATE OF APPLICATION STATUS

November 22, 2019

Hamed Adibnatanzi
1 Sansome Street, Suite 3500
San Francisco, CA 94104

The status of Pre-Application Review Application No. Y19-124 for the addition of commercial floor area and five residential units at 1426 South Main Street, Walnut Creek, is as checked below:

☐	COMPLETE.	Processing will commence as of the date of this letter.
☒	INCOMPLETE.	Upon submittal of the following information, your application may be deemed complete. You will then be mailed another certificate to verify the date when formal processing will begin.

PLANNING

1. General Plan 2025, Figure 11, requires a building setback of 20 to 30 feet (25 feet average) along South Main Street. This issue was previously provided as a requirement on the comments listed in Application No. PRT19-014. The application package did not contain a narrative citing such a request for an amendment to the General Plan. Provide a discussion, illustration, and reasoning for the request.
2. The property is subject to Specific Plan No. 7 (Newell Avenue Specific Plan). The applicable specific plan conditionally allows residential uses.
3. The building height limit is 35 feet on this property. Small projections above this height limit may be allowed to provide building skyline interest. Such an exception would be considered by the Design Review Commission
4. Provide renderings which depict the proposed addition's integration with the existing building. As submitted, the addition appears as a stand-alone building.
5. Provide all existing and proposed building elevations.
6. The proposed building design is unremarkable. Provide a narrative discussing the proposed architecture, its integration with the existing building, and its compatibility with the surrounding environment.
7. Residential balconies (personal outdoor space) should be at least five feet deep to be considered "usable".
8. Review the attached Multi-Family Residential Objective Design Standards (2018Addendum to the Design Review Guidelines). Demonstrate how the proposed project is consistent with each standard or guideline.

9. Discuss or illustrate HVAC equipment installation. Would the equipment be on the roof? Rear elevation? All mechanical equipment shall be architecturally screened from public view.
10. Discuss how the project will propose to address the resulting parking deficiency.
11. Clarify if the subject property has an easement to utilize the south driveway.
12. Parallel parking stalls are required to be 22 feet long. Revise.
13. Submit evidence to the entitlement of the off-site parking stalls (#s 20 thru 23) shown on the plans.
14. Demonstrate how retail patrons would enter the commercial portion of the building. As an example, it is not clear how customers would enter from Stalls 1, 2, or 3. Would they have to walk on the driveway to enter the front of the building? What about from the rear parking lot?
15. A trash enclosure accommodating both the residential and commercial uses will be required. Show where such a trash enclosure would be provided.
16. Each residential unit shall have at least 200 cubic feet of enclosed, weather-proofed and lockable private storage space in addition to guest, linen, pantry and clothes closets customarily provided. Such space may be provided in any location approved by the Community Development Department, but shall not be divided into two (2) or more locations. The balcony storage space appears undersized.
17. Provide conceptual floor plans for the residential units and note the floor area for each unit.
18. A small canopy on the front elevation over the residential access door should be provided.
19. Based on a net new commercial floor area of 3,216 square feet, the estimated Commercial Linkage Fee for affordable housing is $16,080 (3,216 x $5 per sq.ft.).
20. The current Affordable Housing Impact Fee is $18.34 per square-foot of residential living floor area (2019). The rate is adjusted annually in accordance with the California Construction Cost Index.
21. Each residential unit shall be subject to a Traffic Impact Fee. Consult Traffic Engineering for an estimate.
22. This project is subject to the Public Art Ordinance (Ord. 2154, eff. 7/8/2016). This size project must provide art with a value equal to at least one percent of the construction cost or pay a fee in-lieu of providing the art on-site. When the value of the public art would be $50,000 or less, it is encouraged, but not required, that a payment be made to the public art fund. Until July 1, 2021, a person choosing to make a payment to the public art fund instead of providing public art will be allowed to deduct 25 percent from the cost of the public art required under Section 10-10.104. Please contact Steve Huss, the Public Art Manager, at (925)943-5899 x2158 to discuss the process.

ENGINEERING, Mary Ann Bonifacio, P.E., (925)943-5899 x2242

1. Provide an ALTA survey and title report to confirm the property line boundaries and easements. Please note, certain proposed improvements cannot be approved unless easements or agreements exists or are provided as part of the Project.
2. The Project would require a Conditional Use Permit. As a result, the Project is subject to frontage improvements per Section 9-9.205 of the Municipal Code. The property currently has existing frontage, however the frontage shall be reconstructed to comply the City's requirements. The

frontage improvements include but are not limited to the installation of a new **10 ft. wide sidewalk**, driveway, utility relocation, pavement repair to the centerline of South Main Street, striping, street lights, curb and gutter. Frontage improvements shall be constructed per the latest City standards and shown on the improvement plans.

3. Because the sidewalk must be widened to 10 feet, the proposed building addition will need to be redesigned to avoid encroaching into the public right-of-way.
4. The Project shall comply with the requirements of the City Off-Street Parking Standards. The limit of the non-exclusive roadway easement at the north side of the property must provide a minimum 25 ft. from the end of parking stalls #1 thru #3, otherwise the proposed parking stalls must be relocated. In addition, the location of parking stalls #4 thru #7 cannot be approved without an access easement from the adjacent property since there is not adequate clearance for vehicles to access in and out of the parking stalls without encroaching over the property line.
5. Revise the driveway entrance to provide 10 ft. clear behind sidewalk before first parking stall.
6. The Project proposes a one-way entrance on the south side of the property which cannot be approved without an easement and agreement from the adjacent property owner. Please note, further traffic study and traffic coordination may be required by the Traffic Engineer Division if a one-way entrance at the south is proposed.
7. Show all existing features on the site and off-site features within fifty (50) feet of the site boundaries, including structures, roads, trees, designated parking area/stalls (on site and off site parking), striping, underground utilities (i.e. inlets, storm drain lines, water, sewer, etc.), plant life, streambeds, or other significant natural features.
8. Provide dimensions between the proposed building and property lines, proposed building and easements lines, and proposed building and structures.
9. Show the pedestrian ADA path of travel to the proposed building, loading docks, vehicular and service points of ingress and egress. Provide dimensions for driveway widths, drive aisles and indicate direction of travel/internal vehicular circulation.
10. The Project will be subject to provision C.3 Municipal Regional Clean Water Permit. The Project proposes to create/replace more than 2,500 sf but less than 10,000 sf of impervious area (i.e. roof, pavement, concrete), as a result the development can be classified as a small project and is subject to MRP Provision C.3.i which includes an application and permit from the City. The Project would be required to install one or more of the following for the treatment of storm water runoff.
    a. Direct roof runoff onto vegetated areas
    b. Direct runoff from sidewalks, walkways, and/or patios onto vegetated areas
    c. Direct runoff from driveways and/or uncovered parking lots onto vegetated areas
    d. Construct sidewalks, walkways and/or patios with permeable surfaces (i.e. pavers or pervious concrete); construction of bike lanes, driveways and uncovered parking lots with permeable surfaces.
11. The Project shall submit a Storm Water Control Plan for a small land development project. Refer to attachment.

12. Indicate on the plans the location of the existing trash enclosure and the access routes for garbage trucks. The existing trash enclosure will need to be resized to accommodate additional volumes and waste streams (trash, recycle, organics) generated by the building addition.
13. Show locations of proposed utility connections (i.e. sewer, water, fire service, etc.). Note, SB 7 requires water use to be sub-metered for multiunit or mixed-used residential projects and the Project shall allow sufficient space for a private sub-meter system on private property.
14. The Project proposes an entrance to the south of the building which is enclosed by landscape. Please revise.
15. Provide a landscape plan.

Additional comments to be addressed as part of the Improvement Plans (or earlier):

16. A site development permit will be required for this project. All site development shall comply with Title 9 Chapter 9 (Site Development) of the Walnut Creek Municipal Code as determined by the City Engineer. The site development permit is required prior to the issuance of the building permit.
17. An encroachment permit is required for all work within the public right-of-way. The encroachment permit is required prior to the issuance of the site development and building permit.
18. Demonstrate code compliant cross-slopes for all proposed accessible parking stalls and paths of travel.

TRAFFIC ENGINEERING, Yun Na Rhee (925)943-5899 x2219

1. Provide an existing site plan.
2. Per General Plan 2025, Policy 6.2.1, provide a minimum 10-foot wide sidewalk along frontage of property.
3. Indicate where the loading occurs onsite. Show truck turn template into and off site and where it will be loading and unloading.
4. Indicate how the site will address being underparked.
5. Rotate Stall #8 counterclockwise so that it does not back out blindly into the drive aisle.
6. Please show all existing parking onsite (including all adjacent neighbor parking, landscape, etc)
7. Provide shared parking and access agreement for adjacent sites to the north and south of project site.
8. Delete Stall #4 as parking stalls are not allowed within 10 feet from the back of sidewalk.
9. Driveways shall be designed to comply with City Standard CC-3.

Photometric Study:

10. A photometric study will be required for street/right-of-way illumination only. Study area is on Main Street up to centerline, bounded by extension of project property lines. Main Street illumination levels shall be 1.3 average horizontal foot candle (HFC) with a 4 to 1 uniformity ratio (average/minimum). If new streetlights need to be installed it is to be per City standard TS-18.

BUILDING DIVISION, Tim Rodden, P.E., (925)943-5832

1. The upstairs loft apartments are a covered multifamily dwelling as defined in Building Code Section 1102A Building Accessibility: An apartment building with 3 or more dwelling units.

Building Code Section 1104A.2 requires all units on the upper floor to be served by an accessible route. Please amend plans to show a means of vertical access to the apartments such as an elevator.

2. Specify type of construction, occupancy group, fire sprinklers, building area, story height and number of story.

CITY ARBORIST, John Davis, Board Certified Master Arborist, (925)330-1777

1. No comments at this time. An arborist report may be required at a later date depending on whether work within the dripline of trees which line the creek.

OUTSIDE AGENCIES

1. Any comments received will be transmitted by the respective agency under separate cover.

Prior to resubmittal, contact me regarding the size and number of plans for resubmittal. You are welcome to contact me or any of my colleagues above should you have questions or require clarification. I can be reached at (925) 943-5899 ext. 2210 or carreon@walnut-creek.org.

Sincerely,

ALAN B. CARREON
Associate Planner

Attachments
cc: File
City Development Team

Multi-Family Residential Objective Design Standards

Addendum to the Design Review Guidelines

Intent: The list of multi-family residential design standards included in this document is intended to be an addendum to the existing Citywide Design Review Guidelines. The purpose is to fill in identified gaps in the existing document as they relate to current development best practices for market rate and/or affordable multi-family residential projects. Many of the standards relate to the design of multi-family developments that employ urban and mixed-use formats that were not common in Walnut Creek in 1996 when Citywide Design Review Guidelines were adopted.

Format: These are written as objective design standards, not as guidelines. These are therefore mandatory for projects seeking streamlining pursuant to state law, unless the applicant requests exceptions and modifications to these standards through the Design Review process.

Applicability: These standards are applicable to **all** new multi-family residential development, except as provided herein. In addition, they will be included in a checklist for any project requesting approval pursuant to any provision of state law which references objective design standards (including, but not limited to, the Housing Accountability Act or other provisions of Planning and Zoning Law).

Design Review Process: A project that goes through Design Review may request exceptions to the design standards from the Design Review Commission. The City's current discretionary Design Review process will continue to apply to all multi-family residential development projects that do not satisfy the requirements under state law to qualify for streamlined permitting. The City's Design Review process will also be available to any project that is eligible for streamlining pursuant to state law provisions and that seeks exceptions to any of these standards or the City's Design Review Guidelines. Concurrently, it should not be assumed that a project which meets all of the Objective Design Standards will automatically be approved by the Design Review Commission through the design review process. For non-qualifying projects, the Design Review Commission has the discretion to enforce such Standards or not.

ID	Multi-family Residential Design Standard
SITE PLANNING	
Bike Parking	
1	Except in the case of individual locking bicycle lockers and attended bicycle parking, all bicycle parking spaces shall provide a means of securing the bicycle frame and at least one wheel to a securely anchored rack.
2	Where bicycle parking is not visible from the street, directional signage shall be included at the main building entrance.
Vehicular Parking	

1	Controlled entrances to parking facilities (gates, doors, etc.) shall be located a minimum of 18 feet from the back of sidewalk, in order to accommodate one vehicle entering the facility.
2	Except for garage entrances, structured parking shall not be visible from the street, or any adjacent public park, publicly accessible outdoor space or designated open space area. The public -facing elevations of parking structures shall be lined with residential uses on all levels (commercial may be used on the ground floor when allowed by zoning).
3	Structured parking shall be designed such that interior lighting shall be fully shielded and automobile headlamps shall not be visible from adjacent buildings, parcels, streets, public parks, publicly accessible outdoor space or designated open space area.
4	A portion of the required number of parking spaces shall be made available for use by guests, as follows: • 0.10 spaces per dwelling unit for affordable projects (defined as projects reserving at least 50% or more of the units for income-restricted households, as defined under California Law). • 0.15 spaces per dwelling unit for all other projects These guest parking spaces shall be located outside of any security gates or other access limitation devices unless provisions are made to allow a resident to remotely communicate with and provide access to the visiting guest (such as through an intercom and remote control gate, or other similar devices).
5	In the Core Area, no surface parking shall be located between the main building and any street.
Private Outdoor Space	
1	For the purposes of this standard, private outdoor space is defined as outdoor space that is usable and accessible only to building residents and their visitors, but not to the general public. A minimum amount of private outdoor space shall be provided for residential projects as identified in the rate expressed in the table below, and applied to the development as a whole.

	Core Area		Outside Core Area	
	Affordable Projects	All Other Projects	Affordable Projects	All Other Projects
Private Outdoor Space Requirement	100 SF per unit	150 SF per unit	150 SF per unit	200 SF per unit

For the purposes of this standard, an affordable project is defined as one that reserves a minimum of 50% of the units for income-restricted households, as defined by California State Law. Provided this definition is met, the private outdoor space standard applicable to affordable projects would apply to all the units in the project, whether or not they are affordable.

Private outdoor space may be provided as a combination of “personal” and “common” outdoor spaces, defined as follows:

a. ”Common” outdoor space shall be provided with shared access for all building tenants. These include:
   - Courtyards

	• Gardens • Play areas • Outdoor dining areas • Recreation amenities • Rooftop amenities b. ”Personal” outdoor space shall be provided with direct access from the dwelling unit which it serves. These include: • Balconies • Private gardens • Private yards • Terraces • Decks • Porches
2	Unless located on the rooftop, common outdoor spaces shall be designed to be visible from inside the building, such as windows located at building entrances and/or dwelling unit windows.
3	For each common outdoor space provided, a minimum 15-foot dimension is required in at least one direction, with a minimum dimension of at least 10 feet in all other directions.
4	Up to 15% of the common outdoor space may be landscaped using required stormwater treatment planters that are contiguous with the common outdoor space.
5	For each personal outdoor space provided, a minimum dimension of five feet is required in any one direction.
Landscape Design	
1	Required stormwater treatment facilities can be located in publicly accessible outdoor spaces, but shall not be located in private outdoor spaces (common or personal), public rights-of-way, or public access easements. Exceptions include: • permeable paving (as defined by applicable stormwater management standards), which can be used in private (common or personal) outdoor space • landscaped required stormwater treatment planters, which may occupy up to 15% of the common outdoor space
Fences and Gates	
1	Chain link, barbed wire, and razor wire fencing is prohibited.
ARCHITECTURE	
Building Articulation	
1	Buildings over three stories tall shall have major massing breaks at least every 100 feet along any street frontage, adjacent public park, publicly accessible outdoor space, or designated open space, through the use of varying setbacks, building entries

	and recesses, courtyards or structural bays. Major breaks shall be a minimum of five feet deep and 10 feet wide, and shall extend at least two-thirds of the height of the building. Exceptions include: • For buildings with upper stories (above first floor) stepped back at least five feet, the major break need only extend two-thirds of the height of the portion of the front façade that is not stepped back.
2	Buildings shall have minor massing breaks at least every 50 feet along the street frontage, through the use of varying setbacks, building entries and recesses, or structural bays. Minor breaks shall be a minimum of 18 inches deep and four feet wide and extend the full height of the building.
3	Rooflines shall be vertically articulated at least every 50 feet along the street frontage, through the use of architectural elements such as parapets, varying cornices, reveals, clerestory windows, and varying roof height and/or form.
Residential and Mixed-Use Building Frontages	
1	Primary building entrances and associated paths of travel shall be visible from the adjacent street.
2	Within the Core Area, any mixed-use building street frontage greater than 150 feet in length shall have multiple pedestrian entrances to access the businesses or residences in the building. The maximum distance between building entrances along the same frontage shall be no more than 75 feet.
3	Blank walls (facades without doors, windows, landscaping treatments) shall be less than 30 feet in length along sidewalks, pedestrian walks, or publicly accessible outdoor space areas.
4	Storefronts in new mixed-use developments shall contain clear openings and windows for a minimum of 60% of the total area of the first floor facades facing sidewalks, pedestrian walks, or publicly accessible outdoor space areas.
Air, Light and Privacy	
1	Conform to the rear and side setback and courts requirements for primary living room and bedroom windows contained in the MU-R zone, section 10-2.2.2203 of the municipal code. Required private (personal and common) outdoor space and required stormwater treatment facilities may be used to satisfy this requirement.
2	If a dwelling unit has windows on multiple building frontages, operable windows shall be provided on at least two building frontages.
Materials	
1	Mirrored glass is prohibited in order to minimize off-site glare and maximize transparency.
2	Buildings over three stories must provide a ground floor elevation that is distinctive from the upper stories by providing a material change between the first floor and upper floors along at least 75% of the building façade with frontage upon a street, adjacent public park or public open space.
3	Window frames must be recessed a minimum of two inches from the surrounding wall plane.
4	At least two materials shall be used on any building frontage, in addition to glazing and railings. Any one material must comprise at least 20% of the building frontage, excluding windows and railings. A change in material must be offset by a minimum of six inches in depth.

CONTRA COSTA CLEAN WATER PROGRAM

Preparing a Stormwater Control Plan for a Small Land Development Project

Addendum to the Stormwater C.3 Guidebook

December 1, 2012

Introduction

As of December 1, 2012, development projects that create or replace 2,500 square feet* or more of impervious surface (roofs or pavement) must incorporate one or more specified measures to reduce runoff. This requirement is part of municipalities' comprehensive effort to reduce runoff pollution. The requirement is mandated by Provision C.3.i. in the Municipal Regional Stormwater Permit issued by the California Regional Water Quality Control Boards for the San Francisco Bay Region and Central Valley Region.

It is fairly easy to achieve compliance with the stormwater requirements for small land development projects. Compliance for each project must be carefully documented. Please complete the following form and submit it as directed by municipal staff.

*All projects that create or replace 10,000 square feet or more of impervious surface—and auto service facilities, gas stations, restaurants, and uncovered parking lots that create or replace 5,000 square feet or more of impervious surface—are "Regulated Projects," and require a more comprehensive Stormwater Control Plan. See the Contra Costa Clean Water Program *Stormwater C.3 Guidebook*.

Step-by-Step Instructions

The steps are:

1. Fill out the Project Data Form (below) and select one or more runoff reduction measures.
2. Prepare a site plan or sketch. Specify and design the runoff reduction measure you will use to meet the stated minimum requirements.
3. Complete your submittal, which will include:
    - Project Data Form
    - Site Plan or Sketch
    - Completed checklist for each Runoff Reduction Measure selected

► STEP 1: PROJECT DATA FORM AND RUNOFF REDUCTION MEASURE SELECTION

Complete all fields.

Project Name/Number	
Application Submittal Date [to be verified by municipal staff]	
Project Location [Street Address if available, or intersection and/or APN]	
Name of Owner or Developer	
Project Type and Description [Examples: "Single Family Residence," "Parking Lot Addition," "Retail and Parking"]	
Total Project Site Area (acres)	
Total New Impervious Surface Area (square feet) [Sum of currently pervious areas that will be covered with new impervious surfaces]	
Total Replaced Impervious Surface Area [Sum of currently impervious areas that will be covered with new impervious surfaces.]	
Total Pre-Project Impervious Surface Area	
Total Post-Project Impervious Surface Area	
Runoff Reduction Measures Selected (Check one or more)	❑ 1. Disperse runoff to vegetated area ❑ 2. Pervious pavement ❑ 3. Cisterns or Rain Barrels ❑ 4. Bioretention Facility or Planter Box

► STEP 2: DELINEATE IMPERVIOUS AREAS AND LOCATIONS OF RUNOFF REDUCTION MEASURES

Delineate the impervious area. On a site plan or sketch, show the impervious area—for example, a roof, or portion of a roof, or a paved area—that will drain to your runoff reduction measure. Typically these delineations follow roof ridge lines or grade breaks. Alternatively, show the type and extent of pervious paving. An example sketch is attached.

Indicate the location and kind of runoff reduction measure you've selected. At least one option, designed to manage runoff from some amount of impervious area—or to avoid creating runoff—is required.

For each option selected, there is a brief checklist to confirm your design and your submittal meet minimum requirements.

► STEP 3: COMPLETE AND SUBMIT YOUR PLAN


Consult with municipal staff about when and how to submit your Stormwater Control Plan for Small Projects.

Option 1: Disperse runoff from roofs or pavement to vegetated areas.

This is the simplest option. Downspouts can be directed to vegetated areas adjacent to buildings, or extended via pipes to reach vegetated areas further away. Paved areas can be designed with curb cuts, or without curbs, to direct flow into surrounding vegetation.

On the site plan, show:

- ❑ Each impervious area from which runoff will be directed, and its square footage.
- ❑ The vegetated areas that will receive runoff, and the approximate square footage of each.
- ❑ If necessary, explain in notes on the plan how runoff will be routed from impervious surfaces to vegetated areas.



Connecting a roof leader to a vegetated area. The head from the eave height makes it possible to route roof drainage some distance away from the building.

Confirm the following standard specifications are met:

- ❑ Tributary impervious square footage in no instance exceeds twice the square footage of the receiving pervious area.
- ❑ Roof areas collect runoff and route it to the receiving pervious area via gutters and downspouts.
- ❑ Paved areas are sloped so drainage is routed to the receiving pervious area.
- ❑ Runoff is dispersed across the vegetated area (for example, with a splash block) to avoid erosion and promote infiltration.
- ❑ Vegetated area has amended soils, vegetation, and irrigation as required to maintain soil stability and permeability.
- ❑ Any drain inlets within the vegetated area are at least 3 inches above surrounding grade.

Option 2: Permeable Pavement



This option can be easy to install and maintain, cost-effective, and can add aesthetic value to your project. Permeable pavements may include pervious concrete, pervious asphalt, porous pavers, crushed aggregate, open pavers with grass or plantings, open pavers with gravel, or solid pavers.

Show on your site plan:

- ❑ Location, extent and types of pervious pavements.

Confirm the following standard specifications are met:

- ❑ No erodible areas drain on to permeable pavement.
- ❑ Subgrade compaction is minimal.
- ❑ Reservoir base course is of open-graded crushed stone. Base depth is adequate to retain rainfall (3 inches is adequate) and support design loads (more depth may be required).
- ❑ No subdrain is included or, if a subdrain is included, outlet elevation is a minimum of 3 inches above bottom of base course.
- ❑ Subgrade is uniform and slopes are not so steep that subgrade is prone to erosion.
- ❑ Rigid edge is provided to retain granular pavements and unit pavers.
- ❑ Solid unit pavers, if used, are set in sand or gravel with minimum 3/8 inch gaps between the pavers. Joints are filled with an open-graded aggregate free of fines.
- ❑ Permeable concrete or porous asphalt, if used, are installed by industry-certified professionals according to the vendor's recommendations.
- ❑ Selection and location of pavements incorporates Americans with Disabilities Act requirements (if applicable), site aesthetics, and uses.

Option 3: Cisterns or Rain Barrels

Use of cisterns or rain barrels to comply with this requirement is subject to municipality approval. Planning and Building Permits may be required for larger systems.

Show on your site plan:

- ❑ Impervious areas tributary to each cistern or rain barrel.
- ❑ Location of each cistern or rain barrel.


Confirm the following standard specifications are met:

- ❑ Rain barrels are sited at grade on a sound and level surface at or near gutter downspouts.
- ❑ Gutters tributary to rain barrels are screened with a leaf guard or maximum ½-inch to ¼-inch-minimum corrosion-resistant metallic hardware fabric.
- ❑ Water collected will be used for irrigation only.
- ❑ Openings are screened with a corrosion-resistant metallic fine mesh (1/16 inch or smaller) to prevent mosquito harborage.
- ❑ Large openings are secured to prevent entry by children.
- ❑ Rain barrels and gutters are to be cleaned annually.
- ❑ The Contra Costa Mosquito and Vector Control District is informed of the installation. The District will be provided additional information and/or rights of entry if they request.

Option 4: Bioretention Facility or Planter Box

An above-ground planter box may be appropriate if the development site lacks level landscaped areas for dispersion and pervious pavements are not practical. Planter boxes and bioretention facilities can treat runoff from impervious surfaces 25 times their area (sizing factor of 0.04).

Detailed design guidance for planter boxes and bioretention areas is in the *Contra Costa Clean Water Program Stormwater C.3 Guidebook*.



Flow-through planter built into a hillside. Flows from the underdrain and overflow must be directed in accordance with local requirements.

Show on your site plan:

- ❑ Impervious areas tributary to the planter box.
- ❑ Location and footprint of planter box.

Confirm the following standard specifications are met:

- ❑ Reservoir depth is 4"-6" minimum.
- ❑ 18" depth soil mix with minimum long-term infiltration rate of 5"/hour. See http://www.cccleanwater.org/c3-guidebook.html for a list of soil mix suppliers.
- ❑ Surface area of soil mix is a minimum 0.04 times the tributary impervious area.
- ❑ "Class 2 perm" drainage layer 12" deep.
- ❑ No filter fabric.
- ❑ Perforated pipe (PVC SDR 35 or approved equivalent) underdrain with outlet located flush or nearly flush with planter bottom.
- ❑ Connection with sufficient head to storm drain or discharge point.
- ❑ Underdrain has a clean-out port consisting of a vertical, rigid, non-perforated PVC pipe, connected to the underdrain via a sweep bend, with a minimum diameter of 4" and a watertight cap.
- ❑ Overflow outlet connected to a downstream storm drain or approved discharge point.
- ❑ Planter is set level.
- ❑ Emergency spillage will be safely conveyed overland.
- ❑ Plantings are suitable to the climate, exposure, and a well-drained soil.
- ❑ Irrigation system with connection to water supply, on a separate zone.

Useful Resources

The following references may be useful for design. Designs must meet the minimum standard specifications in this supplement to the *Stormwater C.3 Guidebook*.

Contra Costa Clean Water Program Stormwater C.3 Guidebook. Available at http://www.cccleanwater.org/c3-guidebook.html

Start At the Source: Design Guidance Manual for Stormwater Quality. Bay Area Stormwater Management Agencies Association, 1999. Available at http://www.cccleanwater.org/c3-resources.html

Stormwater Control for Small Projects Fact Sheets. Bay Area Stormwater Management Agencies Association, 2012. Available at http://www.cccleanwater.org/c3-resources.html

Concrete Promotion Council of Northern California www.concreteresources.net.

California Asphalt Pavement Association
http://www.californiapavements.org/stormwater.html


Interlocking Concrete Pavement Institute
http://www.icpi.org/

Porous Pavements, by Bruce K. Ferguson. 2005. ISBN 0-8493-2670-2

Example Sketch

The example below illustrates the level of detail required.

Not to Scale



STREETLIGHTING GUIDELINES

From Traffic Engineering , Public Services Department, 1666 N. Main Street, Walnut Creek, CA 94596 (925) 256-3529
Rev. 01/31/17

Goal Statement:

The purpose of this Streetlighting Guidelines is to provide safety and comfort at public and private facilities through consistent applications of street lighting levels for safe pedestrian friendly paths and lighting of public streets. Street lighting shall be provided at a level consistent with the use of the street and the lighting level recommended by the Illuminating Engineering Society. The qualities of street lighting should safeguard, facilitate and encourage vehicular and pedestrian traffic. Street lighting shall be evaluated whenever frontage improvements are required by the City Engineer.

Lighting Levels for Streets

Street lighting shall provide the following minimum maintained average values

ROADWAY CLASSIFICATIONS	UNIFORMITY RATIO (Eavg / Emin)	REQUIRED HORIZONTAL AVERAGE FOOTCANDLE (UNLESS OTHERWISE STATED)	PAST CITY REQUIRED HORIZONTAL FOOTCANDLE
ROUTES OF REGIONAL SIGNIFICANCE	4 to 1	1.3	1.0
ARTERIALS	4 to 1	1.3	1.0
COLLECTOR*	4 to 1	0.6	0.2
Pedestrian Retail District**	4 to 1	2	2
CORE--residential	4 to 1	0.6	0.2
LOCAL ROADS	6 to 1	0.4	0.1
SIDEWALKS	Based on adjacent road way classification	REQUIRED VERTICAL AVERAGE FOOTCANDLE Routes of Regional Significance, Arterial: 1.0 Collector/Core: 0.6 Residential: 0.2	--

*Shadelands business park and Tice Valley Blvd is to provide 1.2 average footcandle as it is a commercial collector zone with 4 to 1 uniform ratio (avg lum/min lum)

**This may include surrounding streets of the Pedestrian Retail District as determined by the Traffic Engineer.


LED Streetlight

1. LED streetlights to be per specified in City standard TS-18, to be Beta Ledway or Navion Roadway.
2. Decorative streetlights to be per specified in City standard TS-19.
3. Applicant to provide an effort to install LED but the final determination will be by the Traffic Engineer to ensure smooth transition.

STREETLIGHTING GUIDELINES

From Traffic Engineering , Public Services Department, 1666 N. Main Street, Walnut Creek, CA 94596 (925) 256-3529
Rev. 4/28/10

ROADWAY CLASSIFICATION MAP FROM WALNUT CREEK GENERAL PLAN 2025
CHAPTER 5 TRANSPORTATION PAGE 5-8



PHOTOMETRIC REPORT REQUIREMENTS

From Traffic Engineering , Public Services Department, 1666 N. Main Street, Walnut Creek, CA 94596 (925) 256-3529
Rev. 1/31/17

The Photometric Report provides existing and proposed street lighting levels at the project site and in the immediate public area. The report is used as a basis in determining the level of improvements needed to meet City Streetlighting Guidelines.

Basic Scope of a Photometric Report :

The report is to be prepared by or under the direction of a registered Professional Engineer or Architect and shall be presented:

- On a 24"x36" plan sheet that will be included in the Site Development Permit Plan Set.
- 1/8" minimum height lettering, 1"=50' Minimum scale

The following shall be included on the Photometric Report:

- Locations and lighting levels of all existing street lights bounded by the limit of the project to the centerline of the street. (study site may be expanded as specified by the City Traffic Engineer.)
- Any adjacent existing streetlights that may spillover onto the study area. **[*see note]**
- New streetlights if existing lights do not meet City Streetlighting Guidelines.
- Lighting levels in HFC units (Average Horizontal foot candle).
- Show location(s) of existing and new service point(s).
- Existing and proposed topography and other details requested by the City Traffic Engineer in order to completely assess the final street light design.
- A table summarizing the uniformity ratio-- Eaverage/Emin, Average Horizontal foot candle, maximum and minimum values for each street or street segment. (refer to City Streetlighting Guidelines)

Streetlight Design:

All components of the street light (including pole, lamps, bases, junction boxes, wirings, luminaires, lenses, service etc) shall comply with the City specifications. The type and brand names of fixtures and the preferred wiring are provided on City Standard Plans TS-18-1, TS-18-2, TS-19-1 and TS-19-2 for the incandescent light fixtures and LEDs. The lighting levels could be achieved by using LED or inductive based on review and approval by the City Engineer. Design of streetlights for private streets may deviate from these standard details on review and approval by the City Engineer.

Ownership/Maintenance

The developer/owner is responsible for all costs of the design, materials, and installation of the street lighting system.

All new developments shall furnish, install and dedicate streetlights to conform with all items as described in City Street lighting Guidelines. Privately owned streets may deviate from City Streetlighting Guidelines but are subject to review and approval by the City Engineer.

The plan shall indicate the rate schedule and the on-going maintenance responsibility of all fixtures for street lights installed on public streets.

The lighting levels for private property including but not limited to private parking lots and /or private garages are subject to the Design Review Commission review and approval.

** Existing adjacent lighting may be obtained from PGE streetlight inventory that the City will provide to the applicant. The spreadsheet contains the existing streetlight technical information such as but not limited to wattage, type of light, pole height, etc.*

The method to obtain the information needed for the existing poles within study area is to conduct a field visit, note the badge number labeled on the pole, and look up the badge number in the PGE streetlight inventory which corresponds to the specific pole and its specification including but not limited to wattage, type of light, pole height, etc.